



AUSTRALIAN RAIL TRACK CORPORATION LTD

## Southern Sydney Freight Line IMPORTANT COMMUNITY INFORMATION

### Sefton Area – Weekend Works

Australian Rail Track Corporation (ARTC) will be undertaking construction works in your area over the weekend of the 24<sup>th</sup> and 25<sup>th</sup> July 2010. These works are part of the construction of the Southern Sydney Freight Line (SSFL).

**Sefton Station** - The works will take place from 7.00am and continue until 5.00pm on Saturday 24<sup>th</sup> July and Sunday 25<sup>th</sup> July 2010. The works will involve installation of inter track drainage at Sefton Station and investigation of existing capping layer. Equipment used will be 7t excavator, rubber tyre dumpy truck, plywood shuttering and hand tools.



**Sefton Station** – The works will take place from 200am on Saturday 24<sup>th</sup> July until 2.00am on Monday 26<sup>th</sup> July 2010. Works to lifts shafts including glazing and cladding. Works to throw screens and power upgrade. The equipment that will be used will be a 60t crane and 20t franna, hand tools, delivery trucks, oxy sets, scaffold and scissor lift.



**Sefton Station** – The works will take place from 7.00am until 7.00pm on both Saturday 24<sup>th</sup> July and Sunday 25<sup>th</sup> July 2010. The works will involve the construction of an underground line crossing. The equipment used will be an excavator, dumpy and hand tools.



**Sefton Station** – The works will take place from 7.00am until 5.00pm on both Saturday 24<sup>th</sup> July and Sunday 25<sup>th</sup> July 2010. The works will piling at Cooper Road overbridge. The equipment used will be 10t piling rig, 7t excavator, dumpy truck, concrete truck, concrete pump and hand tools.



**Sefton** – The works will begin at 7.00am and will continue until 7.00pm on both Saturday 24<sup>th</sup> July and Sunday 25<sup>th</sup> July 2010. The works will involve installation of 5 new Over head wires structures and wiring. The equipment that will be used will be hi rail cherry pickers, Manitou cranes and excavators.



**Sefton East Junction** – The works will begin at 7.00am and continue until 5.00pm on both Saturday 24<sup>th</sup> July and Sunday 25<sup>th</sup> July 2010. The works will involve installation of anti-throw screens on Auburn Road Bridge, construction of pile wall capping beam and repair works to Bankstown Line underbridge abutments, shotcreting to wing wall at Auburn Road Bridge side. The following equipment will be used: concrete truck, grout pump, concrete line pump, shotcrete pump, plywood sheeting, traffic control, 12t excavator, 7t excavator, welding equipment and hand tools.



**Sefton** – The works will begin at 7.00am and continue until 6.00pm on both Saturday 24<sup>th</sup> July and Sunday 25<sup>th</sup> July 2010. The works will involve the installation of GIJ (Glue Insulated Joints). The following equipment will be used: two front-end loaders and hand tools.



We appreciate everyone's patience while we build this important project.

**Further information**

For further information and any enquiries, please call the 24 Hour Information and **Complaints Line 1800 182 543**



Or Email [ssfl@artc.com.au](mailto:ssfl@artc.com.au) or visit [www.ssfl.artc.com.au](http://www.ssfl.artc.com.au)

Translating & Interpreting Service – Please Phone: 131 450